POWER GEN PIC - COTTAM POWER STATION FOUR x 500 MW UNITS

Retford, Nottinghamshire, U.K.

March 1998

SUMMARY

Conveying PFA from an electrostatic precipitator to a silo at low velocity, providing for low pipewear and minimizing maintenance costs.



Mactenn Systems Ltd. Maryville, Tennessee USA

APPLICATION FEATURE

CUSTOMER Power Gen Plc - Cottam Power Station

Four x 500 MW Units

PFA conveying system for a large power utility.

LOCATION Retford, Nottinghamshire, U.K.

INDUSTRY Power Generation

INSTALLATION DATE March 1998

APPLICATION Conveying of P.F.A. from an electro-static

precipitator.

SYSTEM SUMMARY

Nine x Model 85/8 Multi-Ashflo® transporters

arranged on a common 125-mm conveying line.

SYSTEM OBJECTIVES


A) Convey P.F.A. on a continuous basis with reliable operation.

B) Minimize pipe wear.

C) Low maintenance costs.

D) Easy retrofit to replace existing hydraulic system

SYSTEM LAYOUT



MATERIAL CHARACTERISTICS

MATERIAL

Pulverized Fuel Ash

BULK DENSITY (aerated)

850 kg / M³

PARTICLE SIZE

100% below 100 micron

TEMPERATURE

200°C

MOISTURE CONTENT

Less than 1%

FLOWABILITY

Extremely fluid when aerated

ABRASIVENESS

High

SYSTEM DESCRIPTION

The Multi-Ashflo® system is located on the electro-static precipitator of Unit #2. There are three electro-static precipitators: 'A', 'B' and 'C', each having four fields with three hoppers in each field. The first field hoppers remove 80% of the PFA from the gas stream, and it is these nine hoppers where the Multi-Ashflo®system is located. The ash is conveyed via the 125-mm pipeline to a single ash storage silo.

SYSTEM PERFORMANCE

Conveying rate

Normal:

20 tons/hour

Conveying distance

Maximum: 35 tons/hour 171 M including 36 M vertical

Reception point

Single storage silo

Material velocity

4.4 M/S

Phase density

63

Average air consumption

8 NM3/minute

SYSTEM ADVANTAGES

- Proven equipment design ensures years of reliable performance and economy.
- · Pipeline boosters not required.
- Inflatek Valves provide long life with low maintenance costs.
- Low material velocity provides for low maintenance costs.
- System is compact, easy to install and operates in a fully automatic mode requiring no operator attendance.